

# **Precast Concrete Construction and MiC for Public Housing Developments**

by

**Rayson W H WONG**  
(Chief Structural Engineer)

# HA's Precast Concrete Components



香港房屋委員會  
Hong Kong Housing Authority  
Enhanced Precast

1980s – 90s



**Precast Staircase**



**Precast Concrete Façade (PCF)**



**Semi-precast Slab**



**Precast Beam**

Hong Kong Housing Authority Industry Forum

**Innovative Construction Methods for  
Public Housing Developments 2021**

2000 – 2017



**Volumetric Precast Bathroom (VPB)**



**Precast Acoustic Balcony**



**Precast Roof Elements**  
(e.g. water tank)



**Volumetric Precast Kitchen (VPK)**




**Precast Half Landing**



**Precast Partition Wall**

2019 ~ NOW



**Semi-precast Corridor Slab**



**Precast Lift Shaft**



**Precast Structural Wall**  
(with concealed conduit)



# Precast Concrete Components (PCCs)



香港房屋委員會  
Hong Kong Housing Authority



Precast Water Tank



Precast Parapet

## At the Main Roof



Precast Tie Beams



Precast Façade



Volumetric Precast  
Bathroom/Kitchen (VPB+VPK)



Precast Drywall  
(Building Component)




Precast Partition Wall



Semi-Precast Slab



Precast Balcony



Precast Staircase



Precast Half Landing

Hong Kong Housing Authority Industry Forum

Innovative Construction Methods for  
Public Housing Developments 2021

- Insitu Concrete
- Precast Concrete Components  
(inside domestic flat)
- Precast Concrete Components  
(common area)



# Volumetric Precast Concrete Components

With Finishes and BS Components starting *from 2000 onwards*



**Volumetric Precast  
Kitchen (VPB)**



**Volumetric Precast  
Kitchen (VPK)**



**Volumetric Acoustic  
Balcony**



**Lift Shaft**



**Staircase Half  
Landing**




**Water Tank**



# Enhanced Precast Concrete Components (EPCCs)



Enhanced Semi-precast  
Corridor Slab




Enhanced Semi-precast Slab

- Comprising **corridor slab, domestic flat slab, structural wall** and **lift shaft**.
- Adopted for building contracts since **Feb 2020**.




Precast Structural Wall



Precast Lift Shaft

# Evolution of Precast Concrete Components in HA

(Precast Rate ~ 90% on plan)





# Precast Concrete Components (PCCs)



香港房屋委員會  
Hong Kong Housing Authority



Precast Water Tank



Precast Parapet

## At the Main Roof



Precast Tie Beams



Precast Façade



Volumetric Precast  
Bathroom/Kitchen (VPB+VPK)



Precast Drywall  
(Building Component)




Precast Partition Wall



Semi-Precast Slab



Precast Balcony



Precast Staircase



Precast Half Landing

Hong Kong Housing Authority Industry Forum


Innovative Construction Methods for  
Public Housing Developments 2021

- Insitu Concrete
- Precast Concrete Components  
(inside domestic flat)
- Precast Concrete Components  
(common area)

# Typical Construction Programme for a 40-storey block



香港房屋委員會  
Hong Kong Housing Authority







# Volumetric Precast Lift Machine Room (VPLMR)



香港房屋委員會  
Hong Kong Housing Authority

- Mandate to use since early 2021
- Allow earlier completion of LMR and the subsequent lift installation works
- Avoid extensive formwork and falsework and the subsequent removal works





# External Works Precast Elements



**Precast Manhole**



**Precast Cable  
Drawpit**



**Precast Surface Channel**



# List of Precast Concrete Components (PCCs) in HA



香港房屋委員會  
Hong Kong Housing Authority

## PCCs adopted at TYPICAL FLOOR

- 1) *Precast Façade*
- 2) *Semi-Precast Slab*
- 3) *Precast Concrete Wall between Kitchens*
- 4) *Volumetric Precast Bathroom*
- 5) *Volumetric Precast Kitchen*
- 6) *Precast structural wall*

MiC

- 7) Precast Staircase
- 8) Precast lift shaft
- 9) Semi-precast corridor slab
- 10) Precast Half-landing
- 11) Precast Acoustic Balcony
- 12) Precast Partition Wall
- 13) Precast Beam
- 14) Precast Refuse Chutes

## PCCs adopted at ROOF & G/F

- 15) Precast Roof Parapet
- 16) Precast Roof Water Tank
- 17) Precast Roof Staircase
- 18) Precast Panel Wall for Lift Machine Room at Main Roof
- 19) Semi-precast Roof Slab
- 20) Precast Ground Floor Water Tank
- 21) Precast Segmental Water Tank

## PCCs adopted at EXTERNAL AREA

- 22) Precast Manhole / cable drawpit at external area
- 23) Precast Surface Channel
- 24) Precast Hoarding
- 25) Precast Footing
- 26) Precast Hard Paving

# MiC Application in HA

Hong Kong Housing Authority Industry Forum

**Innovative Construction Methods for  
Public Housing Developments 2021**



# Modular Integrated Construction (MiC)

## MiC - Background

A construction method whereby –

- a) Free-standing volumetric modules (with finishes, fixtures, fittings, etc.)
- b) Manufactured off-site
- c) Transported to site for assembly


Buildings Department	Practice Note for Authorized Persons, Registered Structural Engineers and Registered Geotechnical Engineers	ADV-36
----------------------	---	--------

### Modular Integrated Construction

#### Introduction

Modular Integrated Construction (MiC) refers to a construction method whereby free-standing volumetric modules (with finishes, fixtures, fittings, etc.) are manufactured off-site and then transported for constructing buildings. Proven benefits include improved site safety, more efficient and better quality control, shortened construction period, less construction waste, less demand for on-site labour, less disturbance and nuisance to the neighbourhood, etc., not just contributing to the quality and sustainable built-environment but also help ease some of the challenges of the local construction industry. To encourage MiC, the Buildings Department (BD) has formulated streamlined measures and guidelines to facilitate the industry in meeting the relevant standards and requirements under the Buildings Ordinance (BO).

PNAP ADV-36, Buildings Department,  
<https://www.bd.gov.hk/english/documents/pnap/ADV/ADV036.pdf>




[https://www.bd.gov.hk/english/inform/index\\_mic.html](https://www.bd.gov.hk/english/inform/index_mic.html)

# Modular Integrated Construction (MiC)

## MiC and HA PCCs

- **MiC (also PCCs of HA)** is a kind of **Off-site Prefabrication under DfMA**
- **PCCs and MiC** both share the *similar advantages* such as productivity, quality, safety and environmental friendliness
- Under PNAP-ADV36, MiC qualifies to achieve 6% GFA concession should be –
  - ✓ **free-standing** volumetric modules ;
  - ✓ with **finishes, fixtures, fittings**, etc.; and
  - ✓ manufactured **off-site** and then transported for site assembly.
- Volumetric PCCs with fittings e.g. VPB, VPK, are also MiC



**Off-site Prefabrication**




**Volumetric Precast  
Bathroom / Kitchen  
(VPB/VPK)**




# MiC Mock-up

- 2 storeys / 4 Types of Modular Flats
- Total 8 flats (22 modules)
- Fabricated in 惠州
- Commencement - 9 / 2020
- Completion - 12 / 2020
- Assessment of –
  - buildability
  - workmanship
  - quality control
  - joint integrity



香港房屋委員會  
Hong Kong Housing Authority




Hong Kong Housing Authority Industry Forum

Innovative Construction Methods for  
Public Housing Developments 2021

# MiC Mock-up



香港房屋委員會  
Hong Kong Housing Authority



**Module 7 & 9 are the heaviest modules**

Hong Kong Housing Authority Industry Forum

**Innovative Construction Methods for Public Housing Developments 2021**

**Note: All modules are NOT more than the transportation limit of 2.5m width**



# MiC Mock-up



- Completed in Dec 2020

Hong Kong Housing Authority Industry Forum

**Innovative Construction Methods for  
Public Housing Developments 2021**



## (1) Precast Factory Capacity

- Six active factories currently providing PCCs to HA  
(Few have concrete MiC experience)
- Require upgrading of hoisting gantries
- Large storage for modules

Main Contractor	MiC Supplier	Project
Shui On JV	China State Hailong	Residential Care Homes for the Elderly ("RCHE") in Kwu Tung North (8-storey)
Yau Lee	Yau Lee Wah	Disciplined Services Quarters for FSD at Pak Shing Kok in TKO (16/17 -storey)
Yau Lee	Yau Lee Wah	Yen Chow Street Modular Social Housing Project




**Significant investment for factory to produce MiC modules**



## (2) Site Storage

- Congested sites with limited temporary storage area for large scale MiC modules.





## (3) Construction Vehicle Restriction


- Nearby **site constraints** and **road access restriction** (e.g. narrow road) hinder the delivery of MiC modules.






## (3) Construction Vehicle Restriction (Cont'd)

- Cap 374G Road Traffic (Traffic Control) Regulation 55
- Height not exceeding 4.6m
- Starter bar < 32dia.



## (4) Large Footprint of Public Housing Developments


- Public housing blocks generally have more than 20 flat units (70 to 100 modules).
- Lifting and installation of MiC modules are crucial for domestic block to maintain the current **6-day construction cycle**.






## (5) Size of Module

- HA's modular flat to be sub-divided into modules to suit the 2.5m width limit for transportation.



## (6) Dimensional Tolerance Control


- High precision control for multi-face connection.
- Longer installation time compare with smaller modules.






## (7) Additional Touch-up Works

- MiC has notable benefits for projects involving substantial finishes and fitting works.
- HA's developments are of no-frills design without sophisticated fittings and finishes.



## (7) Additional Touch-up Works (Cont'd)

- Damage of pre-apply painting within and outside flat.
- Re-apply painting after installation of modules and concreting required.






# MiC Pilot Project

- Domestic Block : 12 storeys w/ 240 flats
- Commencement : 2021
- Completion : 2024



香港房屋委員會  
Hong Kong Housing Authority



Hong Kong Housing Authority Industry Forum

Innovative Construction Methods for  
Public Housing Developments 2021

# Thank You





# **Statutory Requirements for BS Installations for MiC & Opportunity of BS DfMA for Public Housing Developments**

by

**Henry Y S CHANG**

(Chief Building Services Engineer)

## **PART I : Statutory Requirements for BS Installations for MiC**

## **PART II : Opportunity of BS DfMA for Public Housing Developments**




# **PART I**

## **Statutory Requirements for BS Installations for MiC**

MiC is a construction method that freestanding volumetric modules (with finishes, fixtures, fittings, etc.) manufactured off-site.

### GFA exemption


Electrical conduits and water supply pipes shall be included in the MiC modules while cables, electrical accessories, electrical appliance and town gas pipe are not mandatory.





## Fixed Electrical Installation


- REC/ REW shall ensure MiC electrical assembly be inspected and tested before delivery
- REC/REW shall ensure suitable materials and good workmanship in MiC electrical assembly
- REC/REW to establish with the factory for a quality control and supervision system
- Scope of works among Contractors properly defined
- Electrical Sub-contractor responsible for completed fixed electrical installations



Fixed Electrical Installation

Household Electrical Products

- Electrical Products (Safety) Regulation (Cap. 406G) (“EPSR”) under the Electricity Ordinance (Cap. 406)
- Electrical products such as televisions, refrigerators, electric water heaters should be in compliance with the safety requirements of EPSR
- The products should have valid Certificates of Safety Compliance





## PNAP APP-161

### Fixed Electrical Installation


### Household Electrical Products

### Energy Label Prescribed Products

- Energy Efficiency (Labelling of Products) Ordinance (Cap. 598)
- Prescribed products includes room air conditioners, refrigerating appliances, compact fluorescent lamps, washing machines, dehumidifiers, televisions, storage type electric water heaters, induction cookers
- all products shall bear an energy label
- products from mainland/overseas suppliers or Hong Kong Importer are acceptable



香港房屋委員會  
Hong Kong Housing Authority



## PNAP APP-161

Fixed Electrical Installation

Household Electrical Products


Energy Label Prescribed

Gas Installations

- Gas Safety Ordinance (Cap. 51)
- Domestic gas appliances includes cookers, water heaters, clothes dryers shall bear GU mark
- Propose not to preinstall gas pipes
  - extra union joints for linking up pipeworks would pose higher risk of gas leakage
  - risk of dislocation during transportation



香港房屋委員會  
Hong Kong Housing Authority





## PNAP APP-161

Fixed Electrical Installation

Household Electrical Products

Energy Label Prescribed

Gas Installations

Plumbing Installations

- Internal pipeworks pre-installed in MiC factory
- Specify parts of plumbing work constructed off-site
- Submit supervision plan before commencement of works
- Licensed Plumber visits MiC factory at least once a week
- Interim inspection by WSD agent on concealed pipeworks before covered up



香港房屋委員會  
Hong Kong Housing Authority

PNAP  
APP-161

Fixed  
Electrical  
Installations

- EMSD's Guidance Notes
- Code 26T, CoP

Household  
Electrical  
Products

- EMSD's Guidance Notes

Statutory  
Requirements  
for BS  
Installations

Energy Label  
Prescribed  
Products

- EMSD's Guidance Notes

Gas  
Installations  
and Domestic  
Gas Appliance

- EMSD's Guidance Notes

Fire Services  
Installations

- FSD's C.L. No. 3/2019 "Guidance Notes"

Plumbing  
Installations

- Guide to Application for Water Supply

## PNAP APP-161

Fixed Electrical Installation

Household Electrical Products

Energy Label Prescribed

Gas Installations


Plumbing Installations

Fire Services Installations

- to provide access points, inspection pits or accessible recesses for covered up FSI
- To provide flexible pipe joint, FSI cabling facilities between modules (cable joints not allow on fire resistance cables serving FSI)
- All material/equipment with product listing cert. /records /letter or product approval /acceptance letters by FSD
- RFSIC conduct regular supervision in prefabrication process and record in log book for FSD checking



香港房屋委員會  
Hong Kong Housing Authority





## BS Installations in pilot HA MiC taking consideration of the Statutory Requirements

- a) MiC modules for typical modular flats are proposed in a pilot HA MiC project.
- b) Following BS installations will be pre-installed in the MiC modules –
  - Water Pipes
  - Electrical conduits, cables and wiring accessories
- c) BS sub-contractor is asked to carry out installations in MiC factory

## BS Installations in pilot HA MiC taking consideration of the Statutory Requirements (Cont'd)

### Brief Procurement of Electrical Contractor in the Pilot Project

a.	<b><u>Contract Arrangements</u></b> Continuing Nominated Sub-contract arrangement. Entire electrical work, both in factory and on site, by one single NSC (except concealed conduits by MC as currently practicing)
b.	<b><u>Special Provisions in Tender</u></b> MiC modules fabrication programme and location of potential factories
	Allow ELNSC having adequate time and liberty to work in factory
	Allow storage area, office area, workshop area for ELNSC
	Factory's administration assistance for customs clearing and tax reporting



## BS Installations in pilot HA MiC taking consideration of the Statutory Requirements (Cont'd)

### Brief Procurement of Electrical Contractor in the Pilot Project

- |    |  |
|----|--|
| c. | <p><b><u>Supervision and Inspection of Off-site Works</u></b></p> <p>HA will employ PSP for factory inspection of pre-installed electrical works according to the current HA's standard of inspection in in-situ project</p> |
|----|--|

# **PART II**

## **Opportunity of BS DfMA for Public Housing Developments**

### **Contents**

**Part IIA – MiC**

**Part IIB – DfMA**




## Part IIA - MiC

1. HKHA have identified a suitable MiC pilot project for Public Housing Development which will be commenced soon.
2. A MiC mock-up was completed in December 2020. Some key findings of BS installations were revealed and will be incorporated in the above pilot project.

## MiC mock-up

### (1) Contract Arrangement




- 2 storeys with 4 Types of Modular Flats, total 8 Flats with 22 modules
- Construction was commenced and completed in Sept 2020 and Dec 2020 respectively.
- Works include the design, fabrication, delivery, installation and construction of mock-up



# MiC mock-up

## (2) Scope of study



To assess the Arch, SE and BSE details in respect of -

- a) Buildability
- b) Workmanship
- c) Quality Control
- d) Joint integrity



## MiC mock-up

### (3) Scope of Contractor's BS installation Works

- ✓ Conduits & wiring
- ✓ Electrical accessories
- ✓ Consumer units completed with MCB units
- ✓ Adaptable boxes & termination boxes
- ✓ Plumbing services of water supply pipeworks
- ✗ Towngas installation and wiring for telecom and CABD system are NOT required.

## MiC mock-up

### **(4) Installation – Building Services (Electrical)**


#### Pre-installed cable

Wiring were pre-installed in modules and THREE wiring connection methods were conducted in the mock-up to investigate their pros and cons.



## Method A

Cable reserved above the slab at temporary recessed area.



Pros	Cons
<ol style="list-style-type: none"> <li>1. Less electrical workload in module fabrication stage</li> <li>2. No adaptable box / termination box required for cable connection</li> </ol>	<ol style="list-style-type: none"> <li>1. Safety concern and more electrical workload during module assembly stage               <ul style="list-style-type: none"> <li>• Workers need to climb up and down for cable and conduit connection before insitu topping between modules</li> </ul> </li> <li>2. Water ingress into conduits</li> <li>3. Adequate space (min. 1000mm) should be reserved for conduit and cable connection during modules assembly               <ul style="list-style-type: none"> <li>• for conduit and cable connection at the same time</li> </ul> </li> </ol>

## Method A



Cable reserved above the slab at  
temporary recessed area




Protection of reserved cable



# Method B

Cable reserved below the slab at adaptable box.


RECOMMENDED




Pros	Cons
<ol style="list-style-type: none"><li>1. Less electrical workload in module fabrication stage</li><li>2. No risk of water ingress into conduits and damage to cables during transportation and module assembly<ul style="list-style-type: none"><li>• Conduit end is plugged off</li><li>• Cable is reserved indoor</li></ul></li><li>3. Final cable connection work after MiC module assembly and conduit connection is smooth</li></ol>	<ol style="list-style-type: none"><li>1. Adequate space (min. 600mm) should be reserved for conduit connection during modules assembly (also apply to Method C)<ul style="list-style-type: none"><li>• space between layers of steel bars is congested for conduit connection</li></ul></li></ol>



## Method B



Cable reserved below the slab at  
adaptable box



Protection of reserved cable



## Method B



MiC Modules Assembly before conduit connection




MiC Modules Assembly after conduit connection

- Conduits connection on site during MiC Modules Assembly



## Method C

Similar to Method B but c/w terminal block in termination box.



Pros	Cons
<ol style="list-style-type: none"> <li>The highest proportion of MiC application amongst the 3 Methods               <ul style="list-style-type: none"> <li>over 90% electrical work was completed during module fabrication stage</li> </ul> </li> <li>Only short length cable (to termination block) is reserved in adaptable box</li> </ol>	<ol style="list-style-type: none"> <li>Space inside termination box is congested</li> <li>Difficult to install/connect cable to terminal block inside termination box               <ul style="list-style-type: none"> <li>Terminal block may required to be removed and reinstalled after cable connection</li> </ul> </li> <li>Bad posture working in a long period of time               <ul style="list-style-type: none"> <li>Workers require body bending upward for cable connection to terminal block</li> </ul> </li> <li>More electrical workload and risk of cable bad contact               <ul style="list-style-type: none"> <li>require additional cable connection to terminal block</li> </ul> </li> <li>More adaptable/termination boxes in ceiling</li> </ol>



Hong Kong Housing Authority Industry Forum  
**Innovative Construction Methods for  
Public Housing Developments 2021**



## Protection of reserved cable



(after cable connection)

## Method C

Joint of Modules

Connect cable to  
terminal block inside  
termination box  
(Module 9)



Adaptable box  
(Module 10)


Cable connection on site during MiC Modules Assembly



# General



Cables with identification labelling



Joint of  
Modules

Conduits with identification labelling




Protection of consumer unit



Protection of electrical accessories

## Pre-installed electrical conduits and accessories



All electrical conduits and accessories (except Telephone points) are pre-installed in modules.


Face plate for:

- Socket outlets
- Lighting switches and points
- TV/FM points
- Connection units (for future A/C units)
- Equipotential bonding
- Door phone unit



## MiC mock-up


### (5) Installation – Building Services (Plumbing)



#### Plumbing (Kitchen & Bathroom)

**Pre-installed:** Internal piping with isolating valves inside flat

**On-site:** All external piping



## Findings of Mock-up

1. All electrical wiring and accessories works in MiC modules could be assembled and connected **without major issue**;
2. Wiring connection with cables reserved below the slab at adaptable boxes between modules (**Method B**) **simplified installation** and **saved connection time**;
3. The back box of pre-installed consumer unit needs to be dismantled and reinstated after wiring work on site at final stage. Installation of consumer unit on site could eliminate abortive work;
4. The **whole process**, including pre-installation of electrical wiring and accessories in MiC modules, the subsequent assembly and connection works was **smooth** and **manageable**;
5. Pre-installation of internal plumbing pipeworks in MiC modules and the subsequent connection works with external pipeworks outside MiC modules could be completed smoothly and manageable without major issue.



## Way Forward

The above key findings of BS installation would be incorporated in the coming MiC pilot project in a Public Housing Development to assess the extra benefits of application of MiC in public housing construction comparing with our current mechanized construction.

## Part IIB - DfMA

Opportunity of application of prefabricated BS installations in Public Housing is being explored and trial implementation of some DfMA BS installations may be conducted to test the suitability if suitable site is identified –

1. DfMA for Electrical installations;
2. DfMA for FS & Water pump installations;
3. DfMA for ACMV installations;
4. DfMA for preassembled lift machine;



## (1) DfMA for Electrical installations

### Current DfMA electrical installations



LV Switchboard in Main switchroom



Emergency Generator, Control Cubicle and Switchgear Assembly

## (1) DfMA for Electrical installations (Cont'd)

### Current DfMA electrical installations (Cont'd)



Prefabricated Cable Riser for domestic floors



Prefabricate Trunking (E-shape)



## (1) DfMA for Electrical installations (Cont'd)

### Current DfMA electrical installations (Cont'd)



2-stage Lighting Control Box



Concealed Conduits and Equipotential Bonding Accessories in Precast Elements




## (1) DfMA for Electrical installations (Cont'd)

### Potential DfMA electrical installations

#### At typical floor meter rooms

- Switchgear assembly for domestic flats together with E-shape trunkings, connecting cables and wooden board for supply company's metering equipment
- Switchgear assembly for general lighting, emergency lighting and small power





## (1) DfMA for Electrical installations (Cont'd)

### Potential DfMA electrical installations (Cont'd)

#### DfMA electrical installations trial at typical floor meter room

- Process of conventional electrical installation work
- Process of DfMA electrical installation work
- Comparison of installation programme on-site

	Man x hours	Man-hour
Conventional	3 man x 3 hours	9
DfMA	5 man x 10 mins (or 0.167 hours)	0.835
	Time saving per meter room (for 8 flats) :	8

## **(1) DfMA for Electrical installations (Cont'd)**

### **Potential DfMA electrical installations (Cont'd)**

#### **DfMA electrical installations trial at typical floor meter room**

- The following benefits were observed in the above DfMA trial exercise / are anticipated in the long run -
  - Enhance construction quality, site safety and working environment for electrical work assembled in factory (off-site)
  - Shorten installation programme on site, hence increase productivity
  - Reduce reliance on local labour
  - Labour cost saving for DfMA mass production in factory



## **(2) DfMA for FS & Water pump installations**

### **Potential DfMA FS & Water pump installations**

#### **At G/F fresh and flushing water pump room**

- Prefabricated PRV sets for fresh water supply
- Prefabricated PRV sets for flushing water supply
- Prefabricated fresh water pump sets
- Prefabricated flushing water pump sets

#### **At G/F fire services up-feed pump room and sprinkler pump room**

- Prefabricated FS upfeed pump sets
- Prefabricated FS fixed & booster pump sets
- Prefabricated sprinkler pump sets

## **(2) DfMA for FS & Water pump installations (Cont'd)**

### **Potential DfMA FS & Water pump installations (Cont'd)**

#### **At Roof fresh water booster pump room**

- Prefabricated fresh water booster pump sets

#### **At G/F sprinkler control room**

- Prefabricated sprinkler control valve sets




## (2) DfMA for FS & Water pump installations (Cont'd)



**Prefabricated Water Pump Module\***

\* Photos courtesy of FEMC



**Prefabricated Pressure Reducing Valve Set Module\***



## (2) DfMA for FS & Water pump installations (Cont'd)

### *Opportunities*

- Alleviating reliance of skilled on-site labour for assembly of water pumps, valves and accessories
- Promoting a safe working environment
- Gaining better quality control and assurance

### *Challenges*

- Making site accessible for the prefabricated modules
- Providing early site access route for delivery of prefabricated modules to water pump room
- Re-scheduling work sequence of water pump installation in building construction programme

### (3) DfMA for ACMV installations

#### Potential DfMA ACMV installations

- Pre-fabricated ductworks
- Pre-fabricated ductwork with exhaust air fan at typical RS&MRR
- Pre-insulated pipes
- Grooved coupling in chilled water pipes
- Pre-fabricated pumpdrop for water pumps
- Cooling tower condensing water pipework system
- Chilled water plant pipework system
- Water pump set and skid with integrated control panel
- Vertical riser module
- Integrated AHU (AHU integrated with LMCP, DDC and valve chamber)
- Modular AHU room

## (4) DfMA for preassembled lift machine

- Conventional Practice for Lift Installation
  - Lift system is assembled in lift machine room
  - Assembly work shall be carried out upon completion of lift machine room
- DfMA Opportunity:
  - Preassembly of lift system off-site
  - The preassembled lift system is delivered and installed upon completion of lift machine room
  - Enhance the construction program since assembly work could be carried out regardless of the progress of lift machine room
- Trial project
  - Trial is being conducted in one HA's project. Installation process is in progress.



## (4) DfMA for preassembled lift machine (Cont'd)

Photos of trial project in a PRH Development



Preassembled Lift Machine





## (4) DfMA for preassembled lift machine (Cont'd)

Photos of trial project in a PRH Development





## Way Forward

The Housing Authority will continue to explore the opportunity of application of DfMA on BS installations for PHD projects. Trial implementation will be conducted if suitable site is identified in order to examine the above mentioned benefits on BS installations.





# Thank You

# **Innovation and Technology (I&T) Adopted in Public Housing Developments**

by

**Dr. Sherman S L YIP**

Chief Architect (Development & Standards)

## Contents

1. Introduction
2. Construction Robotics
3. Development and Construction Site Mobile System (DCSMS)
4. Unmanned Aerial Vehicle (UAV) for Inspecting the Building Envelope
5. Reality Capture for Digitalising As-Constructed/Built Works
6. Building Information Modelling (BIM) – Application & Our Roadmap
7. Looking Forward



## 1. INTRODUCTION

- *The Hong Kong Housing Authority (HA) was established in 1973 under the Housing Ordinance.*
- *The HA plans, builds, manages and maintains different types of public housing.*



## Our Vision

- To provide **affordable rental housing** to low-income families with housing needs, and to help low to middle-income families gain access to subsidised home ownership.

## Our Mission


- To provide **affordable quality housing**, management, maintenance and other housing related services to meet the needs of our customers in a proactive and caring manner.
- To provide an **age-friendly** and **barrier-free** estate environment to address the needs of residents of different ages and physical ability.
- To ensure **cost-effective** and **rational use of public resources** in service delivery and allocation of housing assistance in an open and equitable manner.
- To maintain a **competent, dedicated and performance-oriented TEAM**.

## ***2. Construction Robotics***


## 2. CONSTRUCTION ROBOTICS

### Procurement Strategy for Innovation & Technology

#### Proposed Technical Score - Total 10%



#### Two Envelope Tendering System for "Complex" Building Contract – 65 : 25 : 10





## 2. CONSTRUCTION ROBOTICS

### Construction Robotics Examples in Public Housing Developments



香港房屋委員會  
Hong Kong Housing Authority



### Lift Car Brackets Installation at Lift Well

Trial at Queen's Hill Public Housing Developments

Source: [www.schindler.com](http://www.schindler.com) (Above)



### Water Tightness Test at Bathroom

at Fo Tan Public Housing Developments



Hong Kong Housing Authority Industry Forum

Innovative Construction Methods for  
Public Housing Developments 2021



## 2. CONSTRUCTION ROBOTICS

### Construction Robotics Examples in Public Housing Developments




### External Wall Painting

Trial at Anderson Road Public Housing Developments (Left)


## 2. CONSTRUCTION ROBOTICS

### Potential Applications of Construction Robotics in Public Housing Developments



#### Floor Finishing

Source: [www.fcl.ethz.ch](http://www.fcl.ethz.ch) (Above)



#### Internal Wall Painting

Source: [www.turingcat.com](http://www.turingcat.com) (Above)

<https://www.youtube.com/watch?v=hm9ZSN37jVM> (Below)



### ***3. Development and Construction Site Mobile System (DCSMS)***

### 3. DEVELOPMENT & CONSTRUCTION SITE MOBILE SYSTEM (DCSMS) DCSMS – Background

DCSMS

Development and Construction Site Mobile System

發展及建築  
工地流動系統






### 3. DEVELOPMENT & CONSTRUCTION SITE MOBILE SYSTEM (DCSMS)

#### DCSMS – Our Roadmap

- Mobile-enabled common platform for communication, streamline workflow and improve productivity and traceability in site inspection





### 3. DEVELOPMENT & CONSTRUCTION SITE MOBILE SYSTEM (DCSMS)

## DCSMS – A Centralized Data Processing & Storage System


### The Workflow with DCSMS



Request for Inspection  
to Site Staff



Site Work Inspection



Site measurement/  
record to the Apps



Site record  
supplemented with  
site photos



Site record reflected  
with mark up on  
drawings


### 3. DEVELOPMENT & CONSTRUCTION SITE MOBILE SYSTEM (DCSMS) DCSMS – A Swift Generation of Management Report

#### Replumbing Works:


- Quick Access by Senior Management to monitor site progress
- Dashboard Page with numerical data visualized into graphical data

#### Further Development of DCSMS:


- Site Inspection Progress Dashboard made available to Project Teams for other inspections such as foundation works and flat-to-flat final inspection stage.
- To expand the scope of the DCSMS (from building + building services + structural works to foundation work + building & building services at final inspection stage)
- To Integrate with Apps developed by contractors and other HA's systems



Overview of the work progress



Graphical analysis of the work progress to facilitate monitoring & management



Completion status per each domestic block

## ***4. Unmanned Aerial Vehicle (UAV) for Inspecting the Building Envelope***



## 4. UNMANNED AREIAL VEHICLE (UAV) FOR INSPECTING THE BUILDING ENVELOPE

### Non-construction Application of UAV



香港房屋委員會  
Hong Kong Housing Authority


#### 3D Photorealistic Mesh Modelling

- Wah Fu Estate



#### External Wall Inspection

- Defect detection near completion stage at Hang Kin Street Public Housing Developments





## 4. UNMANNED AERIAL VEHICLE (UAV) FOR INSPECTING THE BUILDING ENVELOPE

### UAV & Artificial Intelligence (AI) with BIM

#### How to Conduct External Wall Inspection:

- Firstly, UAV to scan building external condition of each floor with high resolution data acquisition
- Next, AI to detect defects with locations shown on the BIM/GIS model








## 4. UNMANNED AREIAL VEHICLE (UAV) FOR INSPECTING THE BUILDING ENVELOPE

### UAV Operation for Inspection of External Wall As-built Condition



香港房屋委員會  
Hong Kong Housing Authority




Use GIS+BIM model to create simulated video for view of each spot



Use GIS+BIM model to check whether UAV flight can capture the view



Measurement tools to check the distance to target/ground/buildings







## 4. UNMANNED AREIAL VEHICLE (UAV) FOR INSPECTING THE BUILDING ENVELOPE

### Defects Identification by A.I.



香港房屋委員會  
Hong Kong Housing Authority



While the images captured by UAV are uploaded to Cloud, the AI will “match & locate” the images to the BIM model and generate the AI report .



The AI will compare with BIM model and Reality Model and identify and trace the defects with marker tools

### Major Types of Defects Identified by AI




Crack



Peeling



Hole



Defect



Risk

## ***5. Reality Capture for Digitalising As-Constructed/Built Work***

## 5. REALITY CAPTURE FOR DIGITALISING AS-CONSTRUCTED/ BUILT-WORK

### Towards the Age of Mobile Mapping






## 5. REALITY CAPTURE FOR DIGITALISING AS-CONSTRUCTED/ BUILT-WORK

### Application in Public Housing Developments

- Rapid on-site scanning of constructed works
- Scan 1-storey of 26 flats within **30 minutes**
- Applicable for quantity measurement and quality checking



## 5. REALITY CAPTURE FOR DIGITALISING AS-CONSTRUCTED/ BUILT-WORK

### Video of scanning process

### at Chai Wan Road Public Housing Developments





## 5. REALITY CAPTURE FOR DIGITALISING AS-CONSTRUCTED/ BUILT-WORK

### Virtual Site Visit

### at Chai Wan Road Public Housing Developments





## 5. REALITY CAPTURE FOR DIGITALISING AS-CONSTRUCTED/ BUILT-WORK

### External Wall Drainage Inspection Tool

Trial at Upper Wong Tai Sin Estate


- close-up inspections to drain pipes at re-entrant
- identify the location of defective or unauthorized alteration of pipework




Setup at Main Roof



Cage with Camera  
and Wi-fi device



Inspection Tool  
at Re-entrant



Instant Image shown  
in the Apps

## ***6. Building Information Modelling (BIM) – Application & our Roadmap***




## 6. BUILDING INFORMATION MODELLING (BIM) – APPLICATION & OUR ROADMAP


### BIM for Drawing Production




香港房屋委員會  
Hong Kong Housing Authority




BIM Standards and Guidelines



BIM Templates



Software Plug-ins



Single  
source  
of  
truth






## 6. BUILDING INFORMATION MODELLING (BIM) – APPLICATION & OUR ROADMAP



香港房屋委員會  
Hong Kong Housing Authority

### HA's BIM Applications

Our application encompasses full design and construction cycle.



### OUR TARGETS

- Apply BIM to all our projects in 2021
- The extent of BIM application for each project would be determined based on individual projects

## 6. BUILDING INFORMATION MODELLING (BIM) – APPLICATION & OUR ROADMAP

### Reality Capture - Scan to BIM Applications



香港房屋委員會  
Hong Kong Housing Authority

#### Example 1: Laser Scanning for Tree at San Kwai Street Public Housing Developments

- Laser scanning was deployed to create a 3D models of a tree that was clashing with the proposed lift tower;
- With the 3D tree model, our Landscape Architect could easily determine the required extent of tree-pruning to avoid clashing with the proposed lift tower.

**BEFORE**



**AFTER**





## 6. BUILDING INFORMATION MODELLING (BIM) – APPLICATION & OUR ROADMAP

### Reality Capture - Scan to BIM Applications





香港房屋委員會  
Hong Kong Housing Authority

#### Example 2: As-built Verification of Long Span Footbridge at Hoi Tat Estate

**BEFORE**

Traditional 2D plan & section plan



**NOW**

BIM to simulate the in-place installation





## 6. BUILDING INFORMATION MODELLING (BIM) – APPLICATION & OUR ROADMAP


### Reality Capture - Scan to BIM Applications



香港房屋委員會  
Hong Kong Housing Authority

#### Example 3: BIM Simulation for Actual Site Operation at Hoi Tat Estate

Planning by BIM Simulation



Actual Site Operation



## 6. BUILDING INFORMATION MODELLING (BIM) – APPLICATION & OUR ROADMAP



香港房屋委員會  
Hong Kong Housing Authority


### Generative Design

Generative Design is a design process exploring for all possible permutations of a solution and quickly generating design alternatives.


**We wish to explore the generative design to assist our works in the following areas:**

- **Architectural** (Landscape design, Signage & Paving Design);  
Trial at Tai Po Public Housing Developments (below)


#### Signage Design



#### Paving Design



#### Trellis Design







## 6. BUILDING INFORMATION MODELLING (BIM) – APPLICATION & OUR ROADMAP

### Generative Design

- Architectural (Modular Flat Design)

#### Parametric MFD





Hong Kong Housing Authority Industry Forum  
Innovative Construction Methods for  
Public Housing Developments 2021



香港房屋委員會  
Hong Kong Housing Authority

#### Collaboration of MFD data Set & Flat Mix Analysis







## 6. BUILDING INFORMATION MODELLING (BIM) – APPLICATION & OUR ROADMAP

### Generative Design





香港房屋委員會  
Hong Kong Housing Authority

- **Structural Engineering**  
(Foundation Design)



- **Building Services Engineering**  
(Service Routing Design)



## *7. Looking Forward*

## 7. LOOKING FORWARD



*From **Digitisation** to **Digitalisation** through wider use of construction robotics, DCSMS, UAV, remote sensing technology and BIM for construction industry in Hong Kong*





# Thank You