



應用建築信息模擬(BIM) 於水泉澳興建大跨度行人天橋的風險管理



何志偉博士
安全環保部副總經理
2020年11月2日



內容大綱

01

工程概況

02


應用BIM如何優化安全管理

03

例子分享

04


成效



BIM



1.1 背景資料



項目小檔案

工程項目名稱：水泉澳邨二期工程

業主：房屋署

工程內容：興建共5幢住宅大樓，樓高26至30層，合共3459個單位，其中包括興建一條大跨度行人天橋連接水泉澳商場及水泉坳街(毗鄰沙田圍港鐵站)

行人天橋施工內容

工程內容：


1. 天橋的主體結構是由兩條對稱傾斜的拱形鋼管承托一條從山頂通往升降機塔樓的鋼結構組成
2. 升降機塔樓共15層高(約55米高)，由53支工字樁承托
3. 共需耗用2400公噸鋼材(永久及臨時結構各佔50%)
4. 工期約24個月，並於2017年第二季順利竣工

施工難點：

1. 該天橋的升降機塔樓是興建在狹窄的雙線雙程車路與一條受保護的天然溪澗之間
2. 行人天橋跨越天然溪澗及險峭山坡，令工程建造複雜



1.2 工程概況 – 結構簡述





1.3 施工過程中涉及的安全風險



吊運 - 運送臨時及永久結構材料



高空工作 - 安裝、裝修及檢查工序



物料下墜 - 臨時/永久構件/物料、工具



觸電

- 電力焊接
- 手電工具使用

火警

- 焊接工作
- 易燃物品儲存(油漆/隔熱物料/木板)

體力處理

- 搬運鐵器/物料
- 搭建大型棚架

撞倒、絆倒

- 突出物保護
- 物料擺放

其他

- 交通運輸
- 施工對公眾的影響





2.1 應用BIM優化安全管理



- 利用3D動畫模擬施工流程及安排，逐步解釋，令施工人員易於明白安全措施執行要求
- 階段性、針對性培訓不同專業工種人員相關的安全要求



- 選取合適的機械
- 模擬實際操作 (如制定機械操作位置、吊運路徑、物料運送的安排等)





中國建築

CHINA STATE CONSTRUCTION

2. 應用BIM如何優化安全管理

2.2 安全管理工作亮點



吊運安全計劃

- 制定吊運安全計劃書，內容包括吊運管理制度、機械選用、吊運流程、團隊分工及監管要求等

中國建築水泉灣二期地盤

吊運安全計劃 (建造行人橋 "B") 上半部份

中國建築水泉灣二期地盤

吊運安全計劃 (建造行人橋 "B") 下半部份



吊運人員安全培訓

- 吊運訊號員/吊運監督員/起重機操作員書面委任，進行定期培訓及現場表現評估
- BIM動畫用作安全培訓材料
- 使用‘吊運應用表’，優化吊運操作安全

地盤起重裝置安全管理指引

吊鏈 Chain	高古 Shaosha	鋼索 Wire Rope
Grade 8 / 80 以下 安全操作負荷SWL 須每年定期檢驗 吊鉤定期檢查及潤滑	安全操作負荷SWL 須每年定期檢驗	安全操作負荷SWL 須每年定期檢驗
2年	1年	1年
1年	1年	1年
1年	1年	1年

常用吊索安全負荷系數參考

吊索方法 (繩打圈)	繩打圈	繩打圈	繩打圈
夾角	系數	系數	系數
10° <math>\alpha < 60^\circ</math>	100%	50%	100%
60° <math>\alpha < 90^\circ</math>	80%	40%	80%
90° <math>\alpha < 120^\circ</math>	50%	25%	50%

安全操作負荷SWL = 實際SWL × 系數
吊運前，須提高吊索負荷，檢查SWL並確保正確



安全管理工作實施

- 施工方案培訓、風險評估培訓、吊具檢查表及工作安排記錄

安全檢查表

項目	標準	備註
1. 吊具	1. 吊具檢查表	100%
2. 吊具	2. 吊具檢查表	100%
3. 吊具	3. 吊具檢查表	100%
4. 吊具	4. 吊具檢查表	100%
5. 吊具	5. 吊具檢查表	100%
6. 吊具	6. 吊具檢查表	100%
7. 吊具	7. 吊具檢查表	100%
8. 吊具	8. 吊具檢查表	100%
9. 吊具	9. 吊具檢查表	100%
10. 吊具	10. 吊具檢查表	100%

吊運監督員站崗

項目	標準	備註
1. 吊運監督員	1. 吊運監督員	100%
2. 吊運監督員	2. 吊運監督員	100%
3. 吊運監督員	3. 吊運監督員	100%
4. 吊運監督員	4. 吊運監督員	100%
5. 吊運監督員	5. 吊運監督員	100%
6. 吊運監督員	6. 吊運監督員	100%
7. 吊運監督員	7. 吊運監督員	100%
8. 吊運監督員	8. 吊運監督員	100%
9. 吊運監督員	9. 吊運監督員	100%
10. 吊運監督員	10. 吊運監督員	100%



現場監督檢查



現場施工前安全培訓



起重機械每月由公司機械部檢查



吊運監督員站崗



緊急應變計劃

- 制定緊急應變措施
- 報告9天天氣預告
- 風速監察 23Km/h
- 每次吊運前實地進行天氣狀況評估



緊急應變演習



颱風前後安全檢查






中國建築

CHINA STATE CONSTRUCTION

3. 例子分享

3.1 優化工作台設計(減低高空工作的風險)



工作台的設計

- BIM模擬斜拱橋接駁需要焊接的位置細節，有效設計合適工作台及安全進出通道





中國建築

CHINA STATE CONSTRUCTION



3.2天橋拱型結構安裝(提升吊運及高空工作安全管理)



沙田第52區2期

公共租住屋邨 - 水泉澳邨

3月 2015年 — 10月 2015年

電梯塔同時施工

安裝導梁



中國建築工程(香港)有限公司
CHINA STATE CONSTRUCTION ENGRG. (HONG KONG) LTD



3. 例子分享

當導樑架設完成後

- ◆ 在導樑上搭建臨時工作台
- ◆ 利用250噸大型起重機逐步分段組裝拱橋結構部分
- ◆ 完成第一分段後，將整個分段推出
- ◆ 重覆架設臨時工作台
- ◆ 組裝第二分段拱橋後再次推出
- ◆ 完成接駁






中國建築

CHINA STATE CONSTRUCTION



3.3 安裝天橋主體結構(提升吊運及高空工作安全管理)



沙田第52區2期

公共租住屋邨 - 水泉澳邨

3月

2015年

10月

2015年

- ◆ 利用250噸大型起重機吊運第一段橋身組件於導樑上進行組裝
- ◆ 推出第一段橋身組件，吊運第二段橋身組件於導樑上
- ◆ 組裝第一及第二段橋身組件
- ◆ 推出已連接的橋身組件，吊運第三段橋身組件於導樑上
- ◆ 重覆上述工序直至所有橋身組件安裝完成
- ◆ 所有駁口均為以半自動焊方法進行



中國建築工程(香港)有限公司

CHINA STATE CONSTRUCTION ENGRG. (HONG KONG) LTD



Render time: 0h 0m 48.8s






中國建築

CHINA STATE CONSTRUCTION




3.4 橋身裝修工序 (防止高空工作及墮物風險)

3. 例子分享



- ◆ 在橋身底部搭建混合吊棚，以密網墊底再以厚木板妥善覆蓋
- ◆ 主結構及所有工作位置以竹棚架和雙層棚網妥善覆蓋
- ◆ 全職棚架合資格人士，每週對棚架進行法定檢查





- 在整個建造工程實現**零**事故、**零**檢控
- 上下拱橋接駁位置**誤差少**於合約要求的**20毫米**
- 施工期間對公眾影響**減至最少**



中國建築
CHINA STATE CONSTRUCTION



THINK SAFE
WORK SAFE
BE SAFE

~完~

謝謝



Title: Safety Forum 2020 for Works Contracts and Property Management Services Contracts

Super Safety Forum 2020 for Works Contracts
and Property Management Services Contracts
2 November 2020

VO: Here is the footage from
“Safety Forum 2020 for Works Contracts and Property Management Services Contracts”
which was held on 2 November 2020

Super Dr. Ben HO
Deputy General Manager, Safety & Environmental Protection Department of
China State construction Engineering (Hong Kong) Limited
Topic: “Use of Building Information Modelling (BIM) for
Risk Management of Erection of Long Span Footbridge at Shui Chuen O Estate”

VO: The Speaker is Dr. Ben HO
Deputy General Manager, Safety & Environmental Protection Department of
China State construction Engineering (Hong Kong) Limited
His presentation topic is
“Use of Building Information Modelling (BIM) for Risk Management
of Erection of Long Span Footbridge at Shui Chuen O Estate”

Dr. HO: Hello, guests and
Friends of the industry who are joining us online
Today, I am representing my company to share with you
a project that we completed a few years ago
It was the construction of a long-span footbridge at Shui Chuen O
In the process, we used Building Information Modelling (BIM) for safety management
Today, I am going to introduce briefly the project

and talk about during the planning and construction stages
how we dealt with various high-risk items and how
we carried out the planning work for the construction project

In view of time, I have extracted a clip to share with you
It was the BIM animation of the footbridge when it was built
This project was completed smoothly a few years ago
Sharing with you the BIM results
This was a project of the Housing Authority (HA) at Shui Chuen O Estate Phase 2
where there were 5 residential buildings
Each of them ranged from 26 to 30 floors high, with a total of 3459 units
This project included constructing a long-span footbridge
which connected Shui Chuen O Plaza with Shui Chuen Au Street
Next to where the current Sha Tin Wai MTR station situated
You can see here the construction works of this footbridge
Its main structure consisted of a pair of symmetrically tilted steel arches
which supported a steel structure
that led from the top of the mountain to the lift tower
The lift tower was 15 floors high, about 55 m in height
It was supported by 53 I-beams
In total, the project used 2,400 tonnes of steel
Permanent and temporary structures each took up around 50%
The project lasted for around two years
It was completed successfully in Q2 of 2017, three years ago

As you can see in the picture on the left where was the lift tower of the footbridge built? Actually, it was between a narrow road with two-lane two-way traffic and a natural stream that was under protection. The main part of this footbridge spanned over this natural stream and a steep slope. All these environmental factors added to the complexity of the construction works. This image shows the basic structure of the footbridge. There were 14 arch-shaped structural components. The footbridge itself was the main structure and these permanent connecting rods were extended from the arch structures. They provided support for the entire footbridge. There were also some pile foundation and other temporary works including 12 temporary tension piles on the side of the slope which helped to support the main structure of the footbridge. There were also 9 temporary H-piles at the bottom of the tower that helped support this temporary steel tower. Here you can see a temporary metal platform that was mainly used for setting up the cranes and for depositing materials. As you can see a temporary steel tower platform marked in green.

This platform was mainly for the welding of the arch structures and some other finishing work processes in the later stages of the project. Also, there was a steel gear that could be adjusted. The connecting part was used for making minor adjustments. On the whole, the construction of this footbridge involved certain safety hazards coincided with the theme of forum today. There were safety risks related to the lifting operations, the transport processes for temporary and permanent components and materials. There was work at height, some processes of installation and checks.

and there were also risks of falling objects that could hit the vehicles on the road underneath. Both the temporary and permanent components and materials could fall, the workers' tools may also fall. There were also other risks in the entire construction works such as electrical shock, fire, manual handling issues. Given tight work environment, workers risked bumping into things or tripping. There were also risks relating to the impact of the transport of construction materials into and out of the site on the public. The above was a summary of the risks involved. When planning for construction, the team had used BIM to enhance safety management of the project. This was done in a few ways. First, when planning for construction, BIM was introduced to let the construction team get a clear grasp of the surrounding environment of the footbridge during construction as well as the relationships between certain works procedures and sequencing. In the work planning process, this helped to identify the critical path effectively and to devise relevant emergency arrangements.

The use of BIM also helped the team to carry out comprehensive hazard identification and risk assessment.

which in turn helped with devising specific risk management measures and the safety plan

The biggest advantage BIM provided was that it helped to co-ordinate safety measures with the construction works and let the team know when was the most appropriate time to add protective measures such as working platforms guard rails, safe access or egress routes or fall protection measures, etc It helped the team to recognise the key processes in the construction works so then checks were better conducted, and monitoring was more effective BIM also let us see how the whole works would be carried out on site so it helped us select the appropriate plant Through BIM, site team could pick the suitable crane and also model how a particular model could work in future work processes such as its position and its lifting route We could also model how certain materials are transported In terms of training, the team could use 3D animations to model the work processes and relevant work arrangements to better explain them to our workers Workers could better understand the requirements of safety measures involved 3D modelling allows the team to carry out specific training

at different stages, for different professionals We could devise the most suitable safety training for employees of the same job nature Here, I would also like to introduce to you some of the highlights in safety management for this construction project A lifting safety plan had been devised and implemented Some lifting personnel were appointed such as signallers, lifting supervisors and crane operators Signallers had to satisfy the training requirements stipulated by our company Every month, safety personnel and lifting supervisors would evaluate these appointed signallers practically on site to see if they had any bad habits or if the performance of the signaller can satisfy the requirements of our company

We really carried out this work As I mentioned just now, we used BIM animation for training purposes We used lifting cards like the one here to let signallers and lifting supervisors clearly know different cranes are for different loads and what the angle requirements are This also let them know what the safe working loads are and helped and enhanced their monitoring work For some of the basic works we carried out training on the method statement and risk assessment as well as the checklists for lifting gear and records of works We would ensure everyone is clear of their responsibilities in the work process Furthermore, in terms of monitoring and checking on site We had a safety training for workers every day before starting work

The machinery team of our company would conduct monthly safety checks for the cranes being used on site We arranged for a lifting supervisor to station at each key position in our lifting operations This lifting supervisor would monitor the work of the signaller Also, in emergency cases, we had some contingency measures including the site foremen to check the weather and wind speed daily

to decide whether lifting operations would be carried out that day
I have some examples here for you
We did BIM for some working platform designs
to model the details related to the welding positions for the arches
This helped our team design proper working platforms more effectively
as well as the safe access and egress routes
Another example shows
how we made special arrangements
for the installation of the arch-shaped footbridge
It enhanced the safety management of lifting operations and working at height
This animation shows that after the launching beam was designed
we modelled constructing a temporary working platform on top of it
Then, using this 250-tonne crane
we assembled this arch structure piece by piece in various phases
After the first part had been completed, we pushed it out part by part
Next, we repeated these steps to connect a temporary working platform
After assembling the second part, we pushed it out to merge with the first part
This example shows how we installed the main structure of the footbridge
The site used a 250-tonne crane to lift some of the footbridge components
assembled them at the launching beam, then pushed out the first part of the bridge
Then, we lifted the components of the second part onto the launching beam
and then assembled the first and second parts of the footbridge together
We pushed it out and repeated the process with the third part and so on and so forth
As for the welding of the main structure of the bridge,
all the connections were welded together via semi-automatic welding
Here you can also see some of the renovation procedures for the bridge deck
A metal and bamboo scaffold was erected at the bottom of the deck
Considering weight limitation, we added a mesh at the bottom
and then covered it securely with a thick wooden plank
This main structure and all the working positions of
the double-row bamboo scaffolding were securely covered with nets
We arranged a competent person of bamboo scaffolding to be full time on site
to supervise the erection of the bamboo scaffolding
We also asked this competent person
to do weekly checks for the bamboo scaffolding and to sign a Form No. 5
In view of time constraints, I will conclude here
Over the course of around two years
this construction contract had zero incidents and zero prosecutions
In terms of quality, we achieved seamless welding
of the top and bottom arches, which was very hard to achieve
Our margin of error was less than the 20 mm allowed in our contract
Also, throughout the construction process
we strived to minimise any impact on the general public
This brings me to the end of my sharing today, thank you

VO: Thank You For Watching