

Risk Management for Erection of the Footbridge FB1 at NWK

Presented By :

Richard Fung & Ben Fong

We Build, We Serve, We Create



Content

- 1 Particulars of Footbridge FB1
- 2 Risk and Constraint of Traditional Construction Method
- 3 Proposed Innovative Construction Method
- 4 Consideration During Fabrication Works
- 5 Safety Consideration For Site Erection Works





Particulars of Footbridge FB1 – Layout Plan





Particular of Footbridge FB1 - Elevation



Particulars of Footbridge FB1 - Highway Under Footbridge





Risk & Constraint For Traditional Construction Method



Yau Lee Construction Co., Ltd.

High Risk of Traditional Method

- Limited headroom for temporary pier support construction under Highway Structure
- Temporary Pier Support very close to MTR Airport Railway Lines and normal work hours are between 1:45am to 4:30am.
- Limit of Time of occupying Public Road for Erection of Temporary Pier Support and Footbridge Structure. Works to be carried out only at night with many times of road lanes closure.

Proposed Innovative Construction Method



Consideration During Fabrication Works



Weight and Length of Segments are so fabricated such that they can be handled and transported to site.



Consideration During Fabrication Works - Trial Assembly



Trial Assembly of Main Arch



Connection Between Portion B and C

Trial Connection of Working Platform at Portion B to Portion C Connection Point



Consideration During Fabrication Works - Trial Assembly



Point Clouded Model of Factory Assembly by Laser Scan



Laser Scan by Trimble TX5



Yau Lee Construction Co., Ltd.

Safety Consideration For Portion A Erection Works



Assembly of Portion A Main Arch at Site Ground Level



Fenced off lifting zone and supervision by Lifting Supervisor and Safety Officer





Each lifting eye was calculate by engineer ensure CG installation accurately



Installation of Portion A Main Arch

Safety Consideration For Temporary Tower Erection Works



Launching Towers were designed as bolt connected. The structure is assembled at ground level and then lift up to the erection position.



Temporary staircase and cat ladder or aerial platform are prefabricated for access to the working points.



Safety Consideration For Main Structure Erection Works



Steel Platform and Pin Support For Portion C Erection



Metal Scaffolding was erected in cope with Progress of Footbridge Structure Erection





Erection of Footbridge Structure

Safety Preparation Before Lowering Operation



Trial Bolting Up of the Connection for Training the Skilled Worker before the Lowering Operation.



Safety Preparation Before Lowering Operation



Enclosed Platform was erected at Connections between Portion B & C and ensure Full Protection to the Public when carrying out Welding Works



Safety Preparation Before Lowering Operation



Provision of lighting for access tower



Provision of safe access and barriers



Pre-installed barriers and decking for workers safe working on FB1



Preset safety nets on both sides





Lowering Operation – Stage 1 Pushing Footbridge Forward



Stage 1 to be carried out in Day Time 9:00am – 5:00pm





Lowering Operation – TTA For Stage 2







有利建築有限公司 Yau Lee Construction Co., Ltd.

Safety after Lowering FB1



Provision of bamboo scaffold and safety net for safe working at height and public safety



Roll up safety net and check condition before Typhoon no.8



Safety after Lowering FB1





Safety after Lowering FB1





Specific training for high risk process





Paved full protection for hot work safety



Safety After Lowering FB1



Provision of Hoisting Frame with Electric Chain Block for Steel Member Lifting



Provision of Arial Platform for safe working at height



Erection of Canopy



Completion of FB1





Thank You





Title: Safety Forum 2020 for Works Contracts and Property Management Services Contracts

Super	Safety Forum 2020 for Works Contracts and Property Management Services Contracts 2 November 2020
VO:	Here is the footage from "Safety Forum 2020 for Works Contracts and Property Management Services Contracts" which was held on 2 November 2020
Super	Mr. Richard FUNG, Project Manager & Mr. Ben Fong, Senior Safety Officer of Yau Lee Construction Company Limited Topic: "Risk Management for Erection of the Footbridge FB1 at NWK"
VO:	The speaker is Mr. Richard FUNG, Project Manager of Yau Lee Construction Company Limited and Mr. Ben Fong, Senior Safety Officer of Yau Lee Construction Company Limited Their presentation topic is "Risk Management for Erection of the Footbridge FB1 at NWK"
Mr. Fung:	Hello, guests My name is Richard Fung and this is Ben Fong We are here today to share our risk management experience of the Bridge No. 1 construction at Northwest Kowloon site Here is an outline of what we will be talking about today The first part is a general introduction to the bridge The second part is about the risks and limitations of traditional construction methods
	The third part is about an innovative method that we have adopted The fourth and fifth parts are on the safety considerations in production and installation The project scope basically involved 4 public housing blocks 1 Home Ownership block, 1 building complex, 1 recreational facilities building and the Bridge No. 1 extending to Hoi Ying Estate is our focus today This bridge is 145 metres long, with 2 spans The first span is 35 metres long and extends over Hoi Ying Estate The second span is 110 metres long over an expressway OK, let us talk about the geographical environment Because the second span of the bridge was over an expressway we could use traditional construction methods but limitations are numerous This was because we did not have space for falsework From this picture, we can see that in the middle of the bridge there was some space for falsework But if we used traditional construction methods what were the risks and limitations? We can take a look at this cross-section diagram Basically, if we tried to install falsework in this gap the gap was very narrow, so there was limited space There would be a certain degree of risk if we placed machineries there Secondly, the falsework would be located right next to the MTR tracks which were very close and might affect the trains That was quite a big risk
	There would be a certain degree of risk if we placed machineries there Secondly, the falsework would be located right next to the MTR tracks which were very close and might affect the trains That was quite a big risk Thirdly, the bridge was on top of an expressway

so we could not close the road or carry out construction work during the day This means all the work procedures would have to be done at night If we adopted the traditional method we would need to complete the work in phases over many nights We would also need to close the road a lot of times which would disrupt traffic and cause great inconvenience to the public Based on these risks, which we really wanted to eliminate

we came up with a new, innovative way of construction The main structure of the bridge could be constructed vertically so most of the procedures could be completed within our site thus minimising the negative impact on the public On the left, you can see that the first span was basically constructed using the traditional method The second span was constructed vertically You can see part of it on the left, on top of Hoi Ying Estate The other part was on our Northwest Kowloon site Before construction, we had to consider lifting and transportation issues Before production, we calculated the safe working load of lifting on site We could then produce based on our prediction of safe lifting load Another issue was the length of the load we were lifting We had to have an estimated maximum length and we used that length for production in our factory Because accuracy was very important for our new method of construction we made an installation model at the factory We made a smart trial assembly to see if the components we manufactured were the exact same size as what we needed for installation on site in order to reduce the likelihood of error on site We also used 3D scanning, a new technology commonly used We scanned the test installation model at the factory and then we produced a 'Point Cloud Model' We fed it into the computer to compare it against our Building Information Modeling (BIM) It turned out that the test installation model at the factory only had very small differences from our original design model If we completed this step, we could really reduce the risk of alignment errors after the components arriving at site because we had already checked in the factory that what we had made is exactly the same as what was designed After transporting the components to the site we used the traditional method for Part A and we also wanted to reduce the risks of working at height As you can see on the top left, we did a test installation underneath Nearly all the connection points were connected on the ground first and then we lifted them up in two separate loads The load we were lifting was quite large and it was a component that our engineers had designed carefully so that the lifting gear, their centre of gravity, pivot and lifting points were vertical and that it was safe to put down the load During lifting operations, we fenced off the area to make sure no one could enter the lifting zone We would like to mention that for our new method we needed a temporary tower to support the main structure vertically The tower was really big, so we needed to install it in parts

This meant dividing it into 4 to 5 parts and assembling it on the ground as much as possible to reduce the risk of working at height Where possible, we tried to work at lower levels After lifting the load, we usually had a metal working platform

for our workers to do connection works In terms of design, we used bolt connection

so that no welding was needed on site We could minimise welding work during installation and connection Before constructing the main structure we erected a working platform near the ground on the top left corner This allowed workers to work on the platform And later, while building the main structure because it was vertically constructed you can see that there were no real access routes There was not any safe access for us So we built a working platform We then erected a metal scaffolding around the main structure to let workers safely carry out connection and welding work The metal scaffolding was built upwards as the main structure grew taller After the main structure was completed, we dismantled the scaffolding You see that we did a model of the connections too Because when we put the bridge down we only had one night for work, so time management is important We were required to release the road for public use the next morning so we needed to reduce the risk of working overtime We found a space on site to do a model of the connections to train our workers the procedures to figure out how to make improvements to the process and to control how much time we needed to complete it From the experience, we could estimate the time needed that night After we had set the bridge down we had to release the road for the public use the next morning but there was a connection point there that needed welding and touch up How did we solve this problem? We erected a temporary platform beforehand at the connection point The platform had a sliding door After the bridge was assembled and connected We moved the sliding door to connect to the bridge That night, the platform could be put into use immediately and our workers worked on it Afterwards, we could complete the welding procedures on that platform That night, when moving the bridge to a vertical position and putting it down we needed bright lights for the nighttime operation so we installed some lights onto the temporary tower We set up access routes and ladders also to allow our workers to access their working platforms safely While constructing the bridge vertically we provided the platforms with planks and added sufficient safety barriers After the bridge had been set down, our workers could work on top of the bridge Also, for our main structure, we prepared safety nets on top of it

so that after it had been set down, the nets could hang down and there would be instant protection on both sides After completing the vertical construction of the bridge according to our original design, we had to set it down How did we do so? We did it in two steps The first step was Phase 1 where we had to push out the bridge part It was originally set against our temporary tower so we had to push it out first This step was done within our site so that we could do it at daytime without disturbing the public and we could minimise the amount of nighttime work Phase 2 was completed at night For Phase 1, we had to arrange in advance where our workers would be i.e. their standing positions and what tasks to perform when we pushed

Actually, for Phase 1, when we pushed out the bridge we installed a launching platform here so that workers could control that jack at the top On top we had a strand jack It allowed us to loosen the cables that were lifting the bridge

So when we pushed out the bridge the strand jack would start loosening the cables In other words, there was one platform on top and another at the bottom That night, when we set the bridge down, it affected the entire expressway so we had to close the whole road including a total of 16 lanes When we set the bridge down that night, we recorded a video for sharing purposes This was what the bridge looked like, standing up vertically after construction The date was 27 December last year (2019) During the day, from 9:00 a.m. to 5:00 p.m. we pushed the bridge out We first pushed the part that covered Hoi Ying Estate We had equipment monitoring and controlling the operation phase by phase because we could not push it all in one go with this jack We had to do it bit by bit While the bridge was being pushed out, the strand jack loosened the cable Here, in the afternoon, we pushed out Part C That night, we launched the bridge After launching, we started to do connection work Then we prepared some safety nets and hung them down for protection Before the road could be reopened, the safety measures were all installed OK, so this was what the bridge looked like after we lowered it

Mr. Fong: Hello, everyone It is now my turn to talk about the risk management steps we took in the remaining stages after we had lowered the bridge On the left, as mentioned just now we hung down some safety nets then we added bamboo scaffolding on both sides to stabilise the scaffolding nets and prevent objects from falling down On the right was the bamboo scaffolding for the bridge We considered the problem of strong winds during typhoons also So, every time before Typhoon Signal No. 8 was hoisted we asked qualified scaffolders to hang up the scaffolding nets to prevent any impact on the public While working on the bridge we wanted to avoid having unrelated staff up there so we arranged a security guard to station on the deck All the workers on the bridge had to receive the relevant training so that we could tell them what the appropriate work procedures were We issued permits-to-work to specialist staff who had to work on the bridge On the right, you can see we arranged for certain colleagues to do cleaning after work every day so that no loose objects would be blown off the bridge or fall down from it The foremen working on the bridge would also check the deck before they ended work each day and they filled in safety checklists and records every day After our bridge had been launched we had many red falsework to dismantle A lot of complex work procedures to be handled So we had to provide special training for our workers to explain each and every work process to prevent any errors while dismantling parts of the bridge or putting away the cables We had some hot work processes Before doing hot work, we had to add some protection to the bridge to prevent any sparks from falling down and affecting the public passing by below In the middle of the bridge we had to install a covered walkway Since we could not use a crane right in the middle of an expressway we designed a portal frame with an electric chain block It was tested by a registered professional engineer who confirmed that the portal frame could lift our Y-shaped frame and push it to a place further away a special place for installation We also provided elevated work platforms for all work above ground for the safety of our workers You can see on the right of the picture that now, our frame is mostly finished This is a mock-up of what the structure would look like permanently These are the remaining work processes for our bridge It will be completed in December this year That is all of sharing today Thank you

VO: Thank You For Watching